



2017 Solar packages for tiny houses

Basic Install parts+labor \$7600 flat

Includes installation, (6) 270 watt Synthesis solar modules for a cumulative 1.6KW solar array on roof top, Midnite classic charging system, Go Power 3000 watt 115VAC inverter and remote, Battery status monitor, 30 amp transfer switch prewired, 5KW Outback Nano carbon AGM battery bank storage.

Parts Warranty includes: charging system 5 year, inverter 2 year, solar modules 25 year, battery bank 2 year

Labor warranty 90 day hassle free (travel expenses are billable outside 50 miles)

System upgrades (no additional labor)

Add additional battery storage
\$1000 per 5KW battery storage

maximum 15KW total per house due to space restrictions

15KW is equivalence to power output of new Tesla power wall or standard 2 bedroom house consumption for 1 day

Add additional panels

Sold in groups of two \$500 per set

16-23 foot house maximum 6 panels (already included in base system cost)

24-29 foot house can add up 2 extra panels

30 foot or larger can add up to 4 extra panels

Add upgraded inverter

30 amp 4400watt service load Magnum inverter 120/240VAC

\$1200 for unit and remote

Any questions or special accommodations email at gooffgrid@offgridcontracting.com

call us at 865-333-0634 or 865-919-0865